

### LEGEND


- L.P. LOW POINT  
H.P. HIGH POINT  
— DIRECTION OF DRAINAGE  
AP TRELLIS SYSTEM WITH ALUMINUM INFILL PANELS.  
SLOPE TO EDGE @ 1/4" PER FT.

### KEY NOTES

- C1 ALUMINUM CANOPY SYSTEM (COLOR: SEE ELEVATIONS)  
C2 ALUMINUM CANOPY SYSTEM (COLOR: SEE ELEVATIONS)  
DS1 PRIMARY ROOF DRAIN; RE: ELEVATIONS, CIVIL & MEP DRAWINGS (TIE TO UNDERGROUND STORM DRAINAGE)  
LE ACCENT LIGHTING - SEE ELEVATIONS & ELECTRICAL  
L1 - LED LIGHT:  
L1 = SLIM LED (DOWN ONLY)  
L2 = UP ONLY FLOOD FIXTURE  
MF METAL FASCIA  
C1 COLOR:  
C1 = SEE ELEVATIONS FOR COLOR  
C2 = SEE ELEVATIONS FOR COLOR  
ROOF DRAIN OVERFLOW  
S McDONALD'S SIGNAGE BY OTHERS UNDER SEPARATE PERMIT (SEE ELEVATIONS)  
SC INTEGRAL CUTTER SCUPPER; TIE INTO UNDERGROUND STORM DRAINAGE; RE: ELEVATIONS, CIVIL & MEP DRAWINGS

### ROOFING NOTES

- SINGLE-PLY ROOFING SYSTEM WITH BASE FLASHING SHEET EXTENDING UP PARAPET AND TERMINATED UNDER COPING. HOT WELDED TO SEALING STRIP SECURED TO WOOD BLOCKING.
- INSTALLATION OF ROOFING SHALL BE IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS AND PER DETAIL 2 OF THIS SHEET.
- PROVIDE PREFABRICATED METAL CURBS. COORDINATE SIZE, LOCATION AND INSTALLATION REQUIREMENTS W/ M, E, P & S SHEETS. PROVIDE SHIMS TO LEVEL CURB AREAS WHERE ROOF DECK IS PITCHED.
- FOR EXACT LOCATION OF EXHAUST FANS, HVAC UNITS, AND ROOF HATCH. REFER TO STRUCTURAL DRAWINGS.
- CRICKETS MUST BE INSTALLED AT ALL ROOF CURBS & EQUIPMENT PLATFORMS BY GENERAL CONTRACTOR.




### ROOFING SYSTEM

- MANUFACTURERS AND PRODUCTS:  
A. DURO-LAST PVC ROOFING SYSTEM  
B. JM-PVC. REFER TO JOHNS MANVILLE WEBSITE (www.jm.com) FOR MOST UP-TO-DATE INFORMATION.  
NO SUBSTITUTIONS ALLOWED
- SPECIFIED ROOFING SYSTEMS (AS SHOWN):  
HEAT-WELDABLE SINGLE-PLY 50 MIL PVC ROOFING SYSTEM, INSTALLED OVER RIGID INSULATION ON WOOD ROOF DECK HAVING A SLOPE OF 3/8"/FT. MATERIALS SHALL BE AS FOLLOWS:  
A. SINGLE-PLY ROOFING SYSTEM AS MANUFACTURED BY MANUFACTURER LISTED ABOVE TO COMPLY WITH ASTM E 108 OR UL 790, ASTM D-6878, AND FMG I-90 FOR WIND UPLIFT.  
B. FASTENERS: METAL FASTENERS AND PLATES AS PER MANUFACTURER.  
C. ACCESSORIES: PRE-FABRICATED CURBS, FLASHING, CORNERS, TERMINATION BARS, PIPE FLASHING, VENT FLASHING ETC. AS PER MANUFACTURER.  
D. PLEASE SEE SINGLE-PLY FLASHING SPECIFICATIONS FOR A FULL DESCRIPTION OF INSTALLATION INSTRUCTIONS AND REQUIREMENTS WHICH ARE CONSIDERED A PART OF THIS DETAIL.  
E. ANY CARPENTRY OR METAL WORK SHOULD BE DESIGNED AND CONSTRUCTED IN ACCORDANCE WITH LOCAL CODE REQUIREMENTS AND/OR PROJECT SPECIFICATIONS. THESE COMPONENTS SHOULD BE REVIEWED AND APPROVED BY A LICENSED DESIGN PROFESSIONAL. CONTACT MANUFACTURER FOR METAL OPTIONS TO BE INCLUDED WITHIN THE MANUFACTURER'S GUARANTEE.  
F. ROOF MEMBRANE EDGE SEALANT IS REQUIRED ON ALL CUT OR NON-ENCAPSULATED EDGES OF REINFORCED MEMBRANE. THIS INCLUDES FACTORY CUT MEMBRANE
- WALKWAYS:  
A. 30" WIDE WALKWAY ROLL, HOT AIR WELDED TO MEMBRANE.  
B. PROVIDE WALKWAY FROM ROOF LADDER EXIT TO ALL ROOF TOP EQUIPMENT AS PER ROOF PLAN ABOVE.  
C. INSTALL WALKWAY ACCORDING TO WALKWAY PAD MANUFACTURER'S WRITTEN INSTRUCTION.
- RIGID INSULATION:  
PROVIDE REQUIRED LAYERS OF POLYISOCYANURATE INSULATION W/ 1/2" "DENSDECK" COVER BOARD TO MEET A MINIMUM CONTINUOUS R-30 VALUE - THICKNESS AS REQUIRED. PROVIDE POSITIVE SLOPE TO ALL ROOF DRAINS. SEE ROOF PLAN. PROVIDE TOP LAYER PROTECTION MATERIAL AS PER MANUFACTURERS RECOMMENDATIONS. BOTTOM LAYER OF INSULATION TO HAVE INTEGRAL THERMAL BARRIER OR APPROVED ROOFING MANUFACTURER'S THERMAL UNDERLAYMENT SHEET. ASSEMBLY SHALL COMPLY WITH UL 1256 OR FMG 4450 AND ASTM C 1289, TYPE I OR II.
- TAPERED INSULATION:  
PROVIDE TAPERED INSULATION AS REQUIRED FOR POSITIVE DRAINAGE TO ROOF DRAINS AS INDICATED PER ROOF PLAN ABOVE. 1/4" PER FOOT MIN. REQUIRED.
- EXHAUST FANS:  
PROVIDE ADDITIONAL LAYER OF ROOF MEMBRANE AROUND EXHAUST FANS AS INDICATED PER ROOF PLAN ABOVE.

THIS DETAIL IS ALSO SUITABLE FOR TERMINATION OF FLEECE BACKED MEMBRANES. NON FLEECE BACK MEMBRANE IS REQUIRED FOR WALL FLASHINGS.

2 ROOFING SYSTEM  
A1.3 N.T.S.



**Castles Design Group**

A Professional Corporation  
3801 Kirby Dr., Suite 600  
Houston, Texas 77098  
Tel: 713 664 7974  
Fax: 713 664 9756



PREPARED BY: J. Manville  
© 2024 McDonald's USA, LLC  
**McDonald's USA, LLC**  
These drawings and specifications are the confidential and proprietary property of McDonald's USA, LLC and shall not be copied or reproduced without written authorization. The contract documents were prepared by McDonald's USA, LLC and shall govern the project. Use of these drawings for reference or example on another project requires the written consent of McDonald's USA, LLC. The contract documents for reuse on another project is not authorized.

SHEET NO.	TITLE	DRAWN BY	STD	ISSUE DATE	REVIEWED BY	DATE ISSUED	DESCRIPTION	SITE ADDRESS	DATE	BY	DESCRIPTION
A1.3	2024 STANDARD BUILDING - BB20 4584-WOOD/WOOD	JM		2024_04		08 30 2024	WOOD BEARING WALLS W/HARDIE BOARD EXTERIOR FINISH WOOD ROOF TRUSS FRAMING STUCCO/PATENT/METAL PANEL/HARDIE BOARD EXTERIOR FINISH	700 US Highway 69, Huntington, TX 75849	042-3437.00.0		